# Simulated Runoff Testing: Performance Testing of Green Stormwater Infrastructure in Controlled Conditions Benjamin Yezuita<sup>1</sup>, Stephen White<sup>2</sup>, Chris Bergerson<sup>2</sup>



The Philadelphia Water Department has taken steps to reduce combined sewer overflow through the means of Green Stormwater Infrastructure. Stormwater management practices (SMPs), such as rain gardens and underground tree trenches, are designed to capture stormwater, promote infiltration and evapotranspiration, or slowly release stormwater into gray infrastructure after the peak intensity of the storm. In accordance with PWD's Comprehensive Monitoring Plan (CMP), monitoring is being conducted on certain SMPs to validate that their performances meet the design standards. For a SMP on Hewson Street in the Kensington area of Philadelphia, a simulated runoff test (SRT) was conducted to determine the performance of the infiltration stormwater tree trench. Standardized monitoring methods coupled with metered flow into the system allowed for the calculation of the recession rate of water out of the SMP.

### Introduction

A Simulated Runoff Test (SRT) imitates a storm of specific intensity over the measured drainage area of the SMP. Monitoring techniques are used to determine the rate of water entering and leaving the system. SRT methods are derived from methods used by Portland Oregon's Bureau of Environmental Services [1] and are intended to be easily applicable to a variety of stormwater management practices.



Figure 1. Photograph of SRT configuration

### Methods

Methods used are from PWD's CMP [2]. Using the Sensus WL-1250 portable water meter tester seen in Figure 1, a metered flow of 741 cubic feet (CF)(a volume equivalent to a 1"/hour storm over the drainage area of the system's feeding inlets) was applied to the system. This is half of the SMP's design storage capacity.

In order to measure the changing volume of water stored within the trench, water level sensors set to record on a one-minute time interval were installed in the Observation Well (OW1), Cleanout 1\* (CO1), and Green Inlet 2 (GI2)(Fig. 2). Manual measurements using electronic water tape were taken at these locations every 10 minutes to accurately calibrate the water level data. The changing water level within the system was used to determine the associated change in volume of water stored via a stage to storage curve created from design plans.

\*For this analysis, the Cleanout refers to the vertical section of the perforated distribution pipe shown in Figure 4.

<sup>1</sup> Department of Civil, Architectural and Environmental Engineering: Drexel University, 3141 Chestnut Street, Philadelphia, PA 19104 <sup>2</sup> Philadelphia Water Department, Office of Water Sheds: 1101 Market St. 4th Floor, Philadelphia, PA 19107 phillywatersheds.org

## Abstract






•Sump depth is 10" below the bottom of the trench.

- •Porosity of the stone storage is 0.40.
- •Lateral movement of water leaving the system, while not an rate over time.

storage within the system's distribution pipes and inlets.

interface, of 1.22 in/hr.



**Figure 2.** A labeled plan view of the SRT configuration on Hewson Street.

indirect sources.

infiltration footprint. This was very close to the geotechnical investigation infiltration rate of 1.24 in/hr. A time of travel was observed between the application of flow and a recorded response within the system. This travel time (approximately 5 minutes) can be used when validating inflow observations derived from Rain Gauges and other